



Diotranics Enterprises Limited

Specialist in; borehole drilling and services, Electrical works,
supplies and services, Engineering works, solar backups and services,
cctv, Electric fence, Intercom, Intrusion Plumbing services

Tarino Building Namanga Road
Kitengela
P.O. Box 306 – 00241 Kitengela
Contact: 0721423793/0799524922
Email: info@diotranics.co.ke
Web: www.diotranics.co.ke

PIN NO. P051697866F

QUOTATION

CF/9720/2026,
21/06/2026.

Dear Sir,

RE: QUOTATION FOR BOREHOLE DRILLING IN KATALWA, KITUI COUNTY DRILLING OF APPROXIMATELY 240 METRES BOREHOLE

We appreciate the confidence you have exhibited in requesting us to quote for undertaking the above-mentioned project. We are highly delighted. We shall mobilize to the site immediately after your order and undertake the drilling and equipping of the borehole.

The project will include the following steps to ensure the successful completion of the borehole:

1. **Mobilization of Modern Drilling Rig:** We will mobilize state-of-the-art drilling equipment to the site. This includes transportation and setup of the drilling rig and all necessary ancillary equipment.
2. **Drilling the Borehole:** The drilling will commence as per the site specifications, aiming to reach the agreed terminal depth of 250 meters. Our experienced team will ensure that the drilling process is conducted efficiently and safely.
3. **Installation of Casing:** Once the borehole reaches the terminal depth, we will install high-quality casing to ensure the structural integrity and longevity of the borehole. This casing will prevent the collapse of the borehole walls and protect the water source from contamination.
4. **Test-Pumping Calibration:** After casing installation, we will perform test-pumping to calibrate and ascertain the borehole yield. This process involves pumping water from the borehole at various rates to determine the sustainable yield and the quality of water extracted.
5. **Equipping the Borehole:** Finally, we will equip the borehole with the necessary pumping and water delivery systems. This includes the installation of pumps, pipes, and other accessories required to make the borehole operational and efficient.

QUOTATION FOR DRILLING OF 250M BOREHOLE IN KERIA, NYERI COUNTY

ITEM	PROJECT WORK DESCRIPTION	QTY	UNIT	RATE (KSH)	TOTAL (KSH)
I.	Mobilization of the drilling equipment and personnel to the site and demobilization.	1	Item	94,000.00	94,000.00
II.	Drilling 8" dia Borehole from 0-100m depth	100	Mtrs	3,800.00	380,000.00
III.	Drilling 8" dia Borehole from 100-200m depth	140	Mtrs	3,600.00	504,000.00
IV.	Drilling 8" dia Borehole from 200 to depth	0	Mtrs	3,400.00	Rate only
V.	Supply drilling and domestic water for both drilling and field camp use	Ls	Item	20,000.00	Rate Only

VI.	Anticipated Drilling foam usage for improvement of rock cutting recovery	Ls	Item	20,000.00	Rate Only
VII.	153mm (6') diameter Steel/ Plastic (PVC) casing Pipes	140	Mtrs	2,800.00	392,000.00
VIII.	153mm diameter steel screens class B in Plasma Slots	100	Mtrs	3,000.00	300,000.00
IX.	Installation of Casing and Removal				
X.	a) Installation of non-removal of 10" Surface casings in the event of Borehole Collapse in the collapse zone	Ls	Mtr	9,500.00	Rate Only
XI.	b) Installation of removal of 9" Surface casings in the event of Borehole Collapse in the collapse zone	Ls	Mtr	9,500.00	Rate Only
XII.	Supply and Filling of Gravel Pack	10	Tons	5,000.00	50,000.00
XIII.	Physical Development through Compressor air injection	1	Sum	11,000.00	11,000.00
XIV.	24 Hrs. Test Pumping Calibration, step test, constant and discharge test, recovery test after test pumping	1	Sum	70,000.00	70,000.00
XV.	Construction of Concrete slab and cap	Ls	Sum	10,000.00	Rate only
XVI.	Borehole completion Report and Water Chemical Analysis	1	Sum	10,000.00	Rate Only
Total Sum					1,801,000.00
Less Discount					267,000.00
Total Contract Sum					1,534,000.00

Payment Instructions:

Payments for the contract shall be made using the following bank details:

ACCOUNT DETAILS:

BANK NAME : COOPERATIVE BANK OF KENYA
ACCOUNT NAME : DIOTRANICS ENTERPRISES LTD
ACCOUNT NUMBER : 01192946387900
PAYBILL : 400200
PAYBILL NUMBER : 40068779
BRANCH NAME : DONHOLM
BRANCH CODE : 11087
BANK CODE : 11000
SWIFT CODE : KCOOKENA

Authorized Signature & Name

Authorized Signature & Name –

A. CONDITIONS OF CONTRACT

1. The Authority to Drill Borehole from Water Resources Management Authority (WRMA) and NEMA License are pre-requisites for commencement of Borehole Drilling.
2. Site preparation for accessibility by the machines is the client's responsibility and any cost incurred in the site preparation will be borne by the client.
3. Diotranics does not guarantee the quantity or the quality of water which may be struck during drilling but maximum effort will be employed to develop a viable ground water system.
4. Though our objective is to develop viable ground water system for all our clients, please note that the cost of mobilization, drilling, erection and dismantling of the drilling unit shall be paid in case the borehole unfortunately turns out to be dry or the working situation warrants stoppage of the works or demobilization of the machine.
5. A Non-Refundable Waiting Charge of **Kshs 5,000/= per hour** will apply in case the work stops due to omissions by the client.
6. This quotation shall be valid for a period of **30 (Thirty) days** from the date of issue.
7. Surface casings will only be charged if they are installed in the borehole's collapse zone and any additional depth requested by the client and drilled will be charged as per the specified drilling rates for extra depth.

B. TERMS OF PAYMENT

The agreed total contract sum for the drilling works is **Kshs. 1,534,000.00** (Kenya Shillings: One Million, Five Hundred and Thirty-Four Thousand Only). This contract sum may, however, change in case of modifications to borehole drilling parameters such as depth, surface casing, and the amount of gravel used. The payment structure is as follows:

- 80% of the total contract sum (**i.e., Kshs. 1,227,200.00** [Kenya Shillings: One Million, Two Hundred and Twenty-Seven Thousand and Two Hundred Only]) to be paid for the mobilization of the drilling equipment and personnel to the site.
- 20% of the total contract sum (**i.e., Kshs. 306,800.00** [Kenya Shillings: Three Hundred and Six Thousand and Eight Hundred Only]) to be paid upon completion of borehole drilling works and before the installation of casings.

Disclaimer: The price is subject to changes based on the day's pricing of casing materials, especially in the event of delays in the execution of this project.

